
PARKER SPORTS COMPLEX - PHASE 2 PREPARED FOR: CITY OF PARKER, FLORIDA FEMA DISASTER # 4399DR

CITY COUNCIL


MAYOR, ANDREW KELLY COUNCIL MEMBER/MAYOR PRO-TEM, TONYA BARROW COUNCIL MEMBER, RONALD H. CHAPLE **COUNCIL MEMBER, JOHN HANEY COUNCIL MEMBER, KATY BARRETT**




CONSTRUCTION PLANS



FOR BID PURPOSES ONLY



LOCATION MAP




DATE: 5/3/2024

450 Magnolia Avenue, Panama City, FL 324 CA Number 3142

INDEX OF SHEETS

C0.0	COVER SHEET
1 OF 3	BOUNDARY SURVEY
2 OF 3	TOPOGRAPHIC SURVEY
3 OF 3	TREE SURVEY
1 OF 2	PHASE 1 AS-BUILT SURVEY
2 OF 2	PHASE 1 AS-BUILT SURVEY
C0.1	STORMWATER POLLUTION PREVENTION PLAN
C0.2	STORMWATER POLLUTION PREVENTION DETAILS
C0.3	EXISTING CONDITIONS DEMOLITION SITE PLAN
C1.0	SITE IMPROVEMENT PLAN
C1.1	SITE GRADING & DRAINAGE PLAN
C1.2	SITE UTILITIES PLAN
C1.3	SITE STRIPING PLAN (ALTERNATE ONLY)
C2.0	CONSTRUCTION DETAILS
C2.1	STANDARD DETAILS



FOR: ANCHOR CEI, INC.

DESCRIPTION: COMMENCE AT THE NORTHWEST CORNER OF THE EAST 1/2 OF THE SOUTHWEST 1/4 OF THE SOUTHWEST 1/4 OF SECTION 13, TOWNSHIP 4 SOUTH, RANGE 14 WEST, BAY COUNTY, FLORIDA; THENCE SOUTH OO DEGREES 47 MINUTES 18 SECONDS WEST ALONG THE WEST LINE OF THE EAST 1/2 OF THE SOUTHWEST 1/4 OF THE SOUTHWEST 1/4 OF SAID SECTION 13 FOR 469.46 FEET TO THE POINT OF BEGINNING; THENCE CONTINUE SOUTH OO DEGREES 47 MINUTES 18 SECONDS WEST ALONG SAID WEST LINE FOR 819.54 FEET TO THE NORTH RIGHT OF WAY LINE OF U.S. HIGHWAY NO. 98 (BUSINESS); THENCE SOUTH 89 DEGREES 56 MINUTES 22 SECONDS EAST ALONG SAID NORTH RIGHT OF WAY LINE FOR 659.34 FEET TO THE WEST LINE OF BLOCK D, LAKE DRIVE HEIGHTS, AS PER PLAT RECORDED IN PLAT BOOK 8, PAGE 12 OF THE PUBLIC RECORDS ON FILE WITH THE CLERK OF THE CIRCUIT COURT OF BAY COUNTY, FLORIDA; THENCE NORTH OO DEGREES OT MINUTES 14 SECONDS EAST ALONG SAID WEST LINE FOR 1262.69 FEET TO THE SOUTH RIGHT OF WAY LINE OF LAKE DRIVE (HAVING A 50 FT. RIGHT OF WAY); THENCE NORTH 89 DEGREES 49 MINUTES 55 SECONDS WEST ALONG SAID SOUTH RIGHT OF WAY LINE FOR 636.10 FEET; THENCE SOUTH OO DEGREES 47 MINUTES 18 SECONDS WEST FOR 444.56 FEET; THENCE NORTH 89 DEGREES 12 MINUTES 42 SECONDS WEST FOR 8.50 FEET TO THE POINT OF BEGINNING, CONTAINING 18.821 ACRES, MORE OR LESS.

SYMBOLS & A P.O.C. P.O.B. N S E W SEC. T R SEC. T R SEC. T R SEC. L B NO. LS L B NO. LS L B NO. LD. CONC. MON. R.O.W. t	BBREVIATIONS POINT OF COMMENCEMENT POINT OF BEGINNING NORTH SOUTH EAST WEST SECTION TOWNSHIP OR TANGENT RANGE DEGREES MINUTES OR FEET SECONDS OR INCHES FOUND CORNER LAND SURVEYOR LAND SURVEYOR BUSINESS NUMBER IDENTIFICATION CONCRETE MONUMENT RIGHT OF WAY MORE OR LESS
0	SEWER MANHOLE
•	BOLLARD
×	WATER VALVE
Ą	FIRE HYDRANT
Μ	WATER METER
	SIGN POLE
\diamond	POWER POLE
£	GUY ANCHOR
——Р——	AERIAL UTILITY LINE

LOCATIONS OF SUBSURFACE FOUNDATIONS HAVE NOT BEEN DETERMINED AND ARE NOT INDICATED HEREON.

A COMPARISON BETWEEN RECORDED DIRECTIONS AND DISTANCES WITH FIELD MEASURED DIRECTIONS AND DISTANCES HAS BEEN MADE. WHERE THEY VARY THE RECORD AND/OR PLAT DIRECTIONS AND DISTANCES ARE SHOWN IN PARENTHESIS.


THE UNDERSIGNED SURVEYOR HAS NOT BEEN PROVIDED A CURRENT TITLE OPINION OR ABSTRACT OF MATTERS AFFECTING TITLE OR BOUNDARY TO THE SUBJECT PROPERTY. IT IS POSSIBLE THERE ARE RECORDED DEEDS, UNRECORDED DEEDS, EASEMENTS, RESTRICTIONS, SETBACKS OR OTHER INSTRUMENTS AND GOVERNMENT REGULATIONS WHICH COULD AFFECT THE BOUNDARIES AND/OR USE OF THE PROPERTY.

BEARINGS SHOWN HEREON ARE BASED ON RTK GPS OBSERVATIONS UTILIZING L-NET GLOBAL NAVIGATION SATELLITE SYSTEM (GNSS) NETWORK REFERENCED TO THE STATE PLANE COORDINATE SYSTEM, FLORIDA NORTH ZONE, NORTH AMERICAN DATUM 1983 (NAD 83), 2007 ADJUSTMENT AND ARE REFERENCED TO THE NORTH RIGHT OF WAY LINE OF U.S. BUSINESS HIGHWAY NO. 98 HAVING A BEARING OF SOUTH 89 DEGREES 37 MINUTES O5 SECONDS EAST.

A REVIEW OF FLOOD INSURANCE RATE MAP NUMBER 12005C0363H FOR BAY COUNTY, FLORIDA, AND INCORPORATED AREAS, COMMUNITY PANEL NUMBER 120011 0363 H, EFFECTIVE DATE: JUNE 2, 2009, INDICATES THAT THE PROPERTY SHOWN HEREON IS WITHIN ZONE X.

BUCHANAN & HARPER, INC. ENGINEERING • PLANNING • SURVEYING • LANDSCAPE ARCHITECTURE CERTIFICATE OF AUTHORIZATION NUMBER: 2372 735 WEST 11TH STREET – PANAMA CITY, FLORIDA 32401 – TELEPHONE (850) 763-7427
THE UNDERSIGNED,
PLAT OF BOUNDARY SURVEY SURVEY SURVEY SURVEYED 10-28-21 DRAWN 11-5-21 IMPROVEMENTS VISIBLE AS SHOWN SURVEYED SCALE 1" = 100'
REVISED
ELEVATION REFERENCE

TERRAMODEL FILE 12519 / LAYER CODE: E3921 BNDY



TOPOGRAPHIC SURVEY OF PARKER SPORTS COMPLEX 4721 BUSINESS HIGHWAY 98 EAST, PARKER, FLORIDA

FOR: ANCHOR CEI, INC.

SYMBOLS & A N S E W ' ' LB NO. CONC. NAVD EL. RCP PVC INV.	BBREVIATIONS NORTH SOUTH EAST WEST DEGREES MINUTES OR FEET SECONDS OR INCHES LAND SURVEYOR BUSINESS NUMBER CONCRETE NORTH AMERICAN VERTICAL DATUM ELEVATION REINFORCED CONCRETE PIPE POLYVINYL CHLORIDE INVERT
•	BOLLARD
\bowtie	WATER VALVE
φ	FIRE HYDRANT
D	WATER METER
.	SIGN POLE
\diamond	POWER POLE
£	GUY ANCHOR
——_P	AERIAL UTILITY LINE
—S	SANITARY SEWER MAIN
× 22.83	SPOT ELEVATION


RTK GPS REFERENCED TO L-NET GLOBAL NAVIGATION SATELLITE SYSTEM ~ NAVD 88

ELEVATIONS AND BENCHMARKS SHOWN HEREON ARE BASED ON THE NOTED ELEVATION REFERENCE. USE OF THE BENCHMARKS FOR VERTICAL CONTROL SHOULD BE PERFORMED IN ACCORDANCE WITH STANDARDS OF PRACTICE FOR PROFESSIONAL SURVEYORS AND MAPPERS AS OUTLINED IN RULE 5J-I1, FLORIDA ADMINISTRATIVE CODE. PRIOR TO UTILIZING THE BENCHMARKS FOR VERTICAL CONTROL, USER SHALL CHECK PROVIDED BENCHMARKS TO ENSURE THAT THEY HAVE NOT BEEN DISTURBED AND THAT THEY ARE RELATIVE TO EACH OTHER.

THE UNDERGROUND UTILITIES SHOWN HEREON HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND VERBAL LOCATION BY THE UTILITY OWNERS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED, ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE. THE SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES.

A REVIEW OF FLOOD INSURANCE RATE MAP NUMBER 12005C0363H FOR BAY COUNTY, FLORIDA, AND INCORPORATED AREAS, COMMUNITY PANEL NUMBER 120011 0363 H, EFFECTIVE DATE: JUNE 2, 2009, INDICATES THAT THE PROPERTY SHOWN HEREON IS WITHIN ZONE X.


BUCHANAN & HARPER, INC. ENGINEERING • PLANNING • SURVEYING • LANDSCAPE ARCHITECTURE CERTIFICATE OF AUTHORIZATION NUMBER: 2372 735 WEST 11TH STREET – PANAMA CITY, FLORIDA 32401 – TELEPHONE (850) 763-7427
THE UNDERSIGNED,
PLAT OF TOPOGRAPHIC SURVEY SCALE I" = 100' SURVEYED 10-28-21 DRAWN 11-5-21 IMPROVEMENTS VISIBLE AS SHOWN
REVISED
REVISED
BEARING REFERENCE
F.BPA JOB NOFILE NOSHEET NO




THE SYMBOL USED TO SHOW TREE LOCATION IN NO WAY REPRESENTS TRUNK SIZE OR SPREAD OF LIMBS.

DETAIL OF TREES									
BUCHANAN & HARPER, INC. ENGINEERING • PLANNING • SURVEYING • LANDSCAPE ARCHITECTURE CERTIFICATE OF AUTHORIZATION NUMBER: 2372 735 WEST 11TH STREET – PANAMA CITY, FLORIDA 32401 – TELEPHONE (850) 763-7427									
THE UNDERSIGNED,									
PLAT OF TREE SURVEY SCALE " = 100" SURVEYED 10-28-21 DRAWN II-5-21 IMPROVEMENTS VISIBLE AS SHOWN REVISED									
REVISEDOFFICIAL RECORDS OF BAY COUNTY, FLORIDA									
F.B. 1168 PA. 14 JOB NO. 12519.02 FILE NO. E 3927 SHEET NO. 3 OF 3									

TERRAMODEL FILE 12519 / LAYER CODE: TREE





FOR: BCL CIVIL CONTRACTORS, INC.

AS-BUILT SURVEY

PARKER SPORTS PARK COMPLEX PHASE I SITE IMPROVEMENTS

SYMBOLS & A P.O.C. P.O.B. N S E W SEC. T R SEC. T R SEC. T R SEC. L B NO. LS LB NO. LD. CONC. MON. R.O.W. t	BBREVIATIONS POINT OF COMMENCEMENT POINT OF BEGINNING NORTH SOUTH EAST WEST SECTION TOWNSHIP OR TANGENT RANGE DEGREES MINUTES OR FEET SECONDS OR INCHES FOUND CORNER LAND SURVEYOR LAND SURVEYOR LAND SURVEYOR LAND SURVEYOR BUSINESS NUMBER IDENTIFICATION CONCRETE MONUMENT RIGHT OF WAY MORE OR LESS
0	SEWER MANHOLE
•	BOLLARD
\bowtie	WATER VALVE
φ	FIRE HYDRANT
Ø	WATER METER
.	SIGN POLE
\diamond	POWER POLE
£	GUY ANCHOR
———P ———	AERIAL UTILITY LINE

LOCATIONS OF SUBSURFACE FOUNDATIONS HAVE NOT BEEN DETERMINED AND ARE NOT INDICATED HEREON.

A COMPARISON BETWEEN RECORDED DIRECTIONS AND DISTANCES WITH FIELD MEASURED DIRECTIONS AND DISTANCES HAS BEEN MADE. WHERE THEY VARY THE RECORD AND/OR PLAT DIRECTIONS AND DISTANCES ARE SHOWN IN PARENTHESIS.

THE UNDERSIGNED SURVEYOR HAS NOT BEEN PROVIDED A CURRENT TITLE OPINION OR ABSTRACT OF MATTERS AFFECTING TITLE OR BOUNDARY TO THE SUBJECT PROPERTY. IT IS POSSIBLE THERE ARE RECORDED DEEDS, UNRECORDED DEEDS, EASEMENTS, RESTRICTIONS, SETBACKS OR OTHER INSTRUMENTS AND GOVERNMENT REGULATIONS WHICH COULD AFFECT THE BOUNDARIES AND/OR USE OF THE PROPERTY.


BEARINGS SHOWN HEREON ARE BASED ON RTK GPS OBSERVATIONS UTILIZING L-NET GLOBAL NAVIGATION SATELLITE SYSTEM (GNSS) NETWORK REFERENCED TO THE STATE PLANE COORDINATE SYSTEM, FLORIDA NORTH ZONE, NORTH AMERICAN DATUM 1983 (NAD 83), 2007 ADJUSTMENT AND ARE REFERENCED TO THE NORTH RIGHT OF WAY LINE OF U.S. BUSINESS HIGHWAY NO. 98 HAVING A BEARING OF SOUTH 89 DEGREES 37 MINUTES 05 SECONDS EAST.

A REVIEW OF FLOOD INSURANCE RATE MAP NUMBER 12005C0363H FOR BAY COUNTY, FLORIDA, AND INCORPORATED AREAS, COMMUNITY PANEL NUMBER 120011 0363 H, EFFECTIVE DATE: JUNE 2, 2009, INDICATES THAT THE PROPERTY SHOWN HEREON IS WITHIN ZONE X.


BUCHANAN & HARPER, INC. ENGINEERING • PLANNING • SURVEYING • LANDSCAPE ARCHITECTURE CERTIFICATE OF AUTHORIZATION NUMBER: 2372 735 WEST 11TH STREET – PANAMA CITY, FLORIDA 32401 – TELEPHONE (850) 763-7427
THE UNDERSIGNED,
PLAT OF AS-BUILT SURVEY SCALE " = 100' SURVEYED II-II-22 DRAWN II-I5-22 IMPROVEMENTS NEWLY CONSTRUCTED IMPROVEMENTS VISIBLE AS SHOWN REVISED
REVISED

TERRAMODEL FILE 12519 / LAYER CODE: E40475HI






STORMWATER POLLUTION PRE	EVENTION NOTES
THESE PLANS HAVE BEEN PREPARED TO ASSIST THE CONTRACTOR IN OBTAINING COVERAGE UNDER THE FDEP GENERIC PERMIT FOR STORMWATER DISCHARGE FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES. IT IS THE CONTRACTOR'S RESPONSIBILITY TO REVIEW THE PERMIT REQUIREMENTS AND MODIFY THESE PLANS AS NEEDED TO BE IN COMPLIANCE WITH THE PERMIT REQUIREMENTS. SITE DESCRIPTION	STABILIZATION A. STABILIZATION MEASURES SHALL BE INITIATED IMMEDIATELY IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTI TEMPORARILY OR PERMANENTLY CEASED AND WILL REMAIN UNDISTURBED FOR 7 DAYS OR MORE. STABILIZE BY CON ADEQUATE AMOUNTS OF MULCH OVER SEED AND PERIODICALLY WATER TO PROMOTE AND MAINTAIN GROWTH OF THE GROUNDCOVER, OR BY THE USE OF AN APPROPRIATE ALTERNATIVE BMP.
 A. SITE LOCATION THE SITE IS LOCATED AT 4721 E BUSINESS HIGHWAY 98, CITY OF PARKER, BAY COUNTY, FLORIDA SECTION 13, TOWNSHIP 4 SOUTH, RANGE 14 WEST LATITUDE: 30°22'37.0"N LONGITUDE: 85°40'41.1"W B. SITE CONDITIONS & ACTIVITIES NARRATIVE: THE EXISTING CONDITION OF THE SITE IS "VACANT LAND". DURING CONSTRUCTION THE SITE WILL BE CLEARED AND GRUBBED. THIS PROJECT WILL HAVE NO 	 B. PERMANENT SOIL EROSION CONTROL MEASURES FOR ALL SLOPES, CHANNELS, DITCHES OR ANY DISTURBED LAND AREA COMPLETED IMMEDIATELY AFTER FINAL GRADING. WHEN IT IS NOT POSSIBLE TO PERMANENTLY PROTECT A DISTU IMMEDIATELY AFTER GRADING OPERATIONS, TEMPORARY EROSION CONTROL MEASURES SHALL BE INSTALLED. ALL PROTECTION SHALL BE MAINTAINED UNTIL PERMANENT MEASURES ARE IN PLACE AND ESTABLISHED.
MAJOR EFFECT ON ANY THE ABUTTING PROPERTIES. WETLANDS/BUFFERS	C. ALL GRASS SLOPES CONSTRUCTED STEEPER THAN 4H:1V SHALL BE SODDED IMMEDIATELY AFTER FINAL GRADE IS ESTAE
NO WETLANDS OR BUFFERS ARE ASSOCIATED WITH THIS PROJECT. SWPPP INTENT	DUST CONTROL A. BARE EARTH AREAS SHALL BE WATERED DURING CONSTRUCTION AS NECESSARY TO MINIMIZE THE TRANSPORT OF FU IN NO CASE SHALL FUGITIVE DUST BE ALLOWED TO LEAVE THE SITE UNDER CONSTRUCTION.
THE INTENT OF THIS SWPPP IS TO COMPLY WITH THE INTENT OF THE GENERIC PERMIT AND TO PREVENT THE RELEASE OF SOILS, TRASH, CHEMICALS, TOXINS AND OTHER POLLUTANTS, BY WATER , AIR, VEHICLE TRANSPORT OR OTHER MEANS THAT CAN IMPACT STORM WATER QUALITY. THE CONTRACTOR SHALL OBTAIN A COPY OF THE GENERIC PERMIT AND RETAIN ON-SITE FOR FUTURE REFERENCE. THE CONTRACTOR SHALL READ AND UNDERSTAND THE PERMIT,	B. AS REQUIRED AFTER COMPLETION OF CONSTRUCTION, BARE EARTH AREAS SHALL BE VEGETATED.
AND ENSURE THAT THE BMP'S ARE INSTALLED AND THE EXECUTION OF THE WORK IS PERFORMED TO MEET THE INTENT OF THE GENERIC PERMIT AND THE SWPPP.	AT ANY TIME BOTH DURING AND AFTER SITE CONSTRUCTION THAT WATERING AND/OR VEGETATION ARE NOT EFFECTIVE IN CONTROLLING WIND EROSION AND/OR TRANSPORT OF FUGITIVE DUST, OTHER METHODS AS ARE NECESSARY FOR SUCH CON SHALL BE EMPLOYED. THESE METHODS MAY INCLUDE ERECTION OF DUST CONTROL FENCES.
POTENTIAL SOURCES OF POLLUTION THE POTENTIAL SOURCES OF POLLUTION THAT MAY REASONABLY BE EXPECTED TO AFFECT THE QUALITY OF STORM WATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITY INCLUDE: SEDIMENT, PESTICIDES, FERTILIZER, PLASTER, CLEANING SOLVENTS, ASPHALT, CONCRETE, GLUE, ADHESIVES, PAINTS, CURING COMPOUNDS, WOOD PRESERVATIVES, HYDRAULIC OIL FLUIDS, GASOLINE, DIESEL FUEL AND KEROSENE. SEQUENCE OF CONSTRUCTION	WASTE MANAGEMENT A. THE CONTRACTOR SHALL ENSURE THAT ALL WASTE AND DEBRIS ARE MANAGED DAILY SUCH THAT THEY WILL NOT IMPAC STORMWATER OR LEAVE THE PERMITTED AREA, AND DISPOSED OF PROPERLY IN ACCORDANCE WITH APPLICABLE STATE AND FEDERAL REGULATIONS.
THE SEQUENCE OF CONSTRUCTION HAS BEEN DEVELOPED AS A GUIDE FOR THE CONTRACTOR. THE CONTRACTOR SHALL SEQUENCE THE CONSTRUCTION AS NEEDED BASED ON BEST MEANS AND METHODS IN ORDER TO BE IN COMPLIANCE WITH STATE AND LOCAL REQUIREMENTS. THE INSTALLATION OR REMOVAL OF BMPS, EARTH DISTURBANCE, GRADING, TEMPORARY STABILIZATION AND PERMANENT STABILIZATION SHALL BE IMMEDIATELY NOTED IN THE SWPPP IMPLEMENTATION LOG. ALL TEMPORARY BMPS SHALL BE REPAIRED AND MAINTAINED UNTIL STABILIZATION HAS OCCURRED AND THERE IS NO RISK OF DISCURDED ADDRESS THE AND AND PERMANENT CONSTRUCTION DEFINITE AND ADDRESS THAT WILL BE INACTIVE FOR 7 DAYS OR MODE	B. THE CONTRACTOR SHALL ENSURE THAT ALL CHEMICALS, OILS, FUELS, HAZARDOUS WASTE, UNIVERSAL WASTE SUBSTANCES ARE PROPERLY MANAGED AND DISPOSED OF IN ACCORDANCE WITH APPLICABLE STATE, LOCAL AN REGULATIONS. THE CONTRACTOR SHALL ENSURE THAT WASTE IS NOT DISCHARGED FROM THE SITE, AND DOES STORMWATER OR GROUNDWATER.
DISCHARGE. TEMPORARILY SEED, IMMEDIATELY AND THROUGHOUT CONSTRUCTION, DENUDED AREAS THAT WILL BE INACTIVE FOR 7 DAYS OR MORE. PERMANENTLY STABILIZE AREAS TO BE VEGETATED AS THEY ARE BROUGHT TO FINAL GRADE. 1. POST A COPY OF THE NOI OR LETTER FROM FDEP CONFIRMING COVERAGE UNDER THE GENERIC PERMIT, AND THE NAME AND PHONE NUMBER OF THE CONTRACTOR'S REPRESENTATIVE RESPONSIBLE FOR EROSION AND SEDIMENTATION CONTROL INSTALLATION AND MAINTENANCE ON A 24 HOUR BASIS.	C. THE CONTRACTOR SHALL PROVIDE APPROPRIATE AND ADEQUATE WASHOUT FACILITIES TO ENSURE THAT CHEMICALS AI NOT DISCHARGED FROM THE SITE, AND DO NOT IMPACT STORMWATER OR GROUNDWATER. (E.G. CONCRETE/MASONR' PAINT WASHOUT, EIFS, ETC.) THE CONTRACTOR SHALL CLEAN UP SPILLS PROMPTLY AND ENSURE THAT WASHOUT PROPERLY MAINTAINED TO PROVIDE ADEQUATE VOLUME TO PREVENT OVERFLOW.
 INSTALL PERIMETER CONTROLS IMMEDIATELY DOWNSTREAM OF THE PLANNED LOCATION OF THE CONSTRUCTION EXIT. INSTALL STABILIZED CONSTRUCTION EXIT. INSTALL PERMITER CONTROLS. THE CONTRACTOR SHALL INSTALL THE REMAINING BMPS AS SHOWN AND AS REQUIRED TO MEET PERMIT REQUIREMENTS. 	D. THE CONTRACTOR SHALL PROVIDE ADEQUATE SANITARY FACILITIES FOR SITE PERSONNEL, MAINTAIN THROUGHOUT COM AND PROVIDE FOR PROPER DISPOSAL IN ACCORDANCE WITH APPLICABLE STATE, LOCAL AND FEDERAL REGULATIONS
SOME BMP INSTALLATIONS MAY NOT BE POSSIBLE AT THE BEGINNING OF THE PROJECT BUT MUST BE INSTALLED AS SOON AS POSSIBLE TO ENSURE COMPLIANCE. 5. INSTALL TEMPORARY STAGING AND STORAGE AREAS. 6. CONSTRUCT AND STABILIZE THE SEDIMENT BASINS AND SEDIMENT TRAPS WITH APPROPRIATE OUTFALL STRUCTURES, IF REQUIRED.	FACILITIES SHALL BE PROPERLY SECURED TO PREVENT TIPPING. E. A SPILL CONTROL AND CONTAINMENT KIT (CONTAINING FOR EXAMPLE, ABSORBENT MATERIAL SUCH AS KITTY LITTER O
 CONSTRUCT AND STABILIZE HYDRAULIC CONTROLS (DITCHES, SWALES, DIKES, CHECK DAMS, ETC.), IF REQUIRED. BEGIN DEMOLITION, CLEARING AND GRUBBING OPERATIONS AS APPLICABLE. BEGIN CONSTRUCTION OF SITE IMPROVEMENTS. 	ACID, BASE, NEUTRALIZING AGENT, BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, PLASTIC AND ME CONTAINERS, ETC.) SHALL BE PROVIDED AT THE CONSTRUCTION SITE AND IT'S LOCATION(S) SHALL BE IDENTIFIED W SIGNAGEAND SHOWN ON THE SITE MAPS. A. THE SPILL CONTROL AND CONTAINMENT KIT SHALL BE OF SUFFICIENT QUANTITIES AND APPROPRIATE CONTENT TO C
 PAVE SITE AND STABILIZE PER PLAN. REMOVE ALL TEMPORARY EROSION AND SEDIMENT CONTROL DEVICES AFTER SITE HAS ACHIEVED FINAL STABILIZATION. SUBMIT NOTICE OF TERMINATION (NOT) ONCE ALL CONSTRUCTION IS COMPLETE AND ALL AREAS ARE STABILIZED PER PLAN. 	A. THE SPILL CONTROL AND CONTAINMENT KIT SHALL BE OF SUFFICIENT QUANTITIES AND APPROPRIATE CONTENT TO C SPILL FROM THE LARGEST ANTICIPATED PIECE OF EQUIPMENT AND FROM THE LARGEST ANTICIPATED QUANTITIES OF STORED ON THE SITE AT ANY GIVEN TIME.
GENERAL NOTES A. IT IS THE CONTRACTOR'S RESPONSIBILITY TO FILE "NOTICE OF INTENT TO USE GENERIC PERMIT FOR STORMWATER DISCHARGE FROM CONSTRUCTION ACTIVITIES" (DEP FORM 62-621.300(4)(B) OR LATEST VERSION) TO FDEP TO THE FOLLOWING ADDRESS OR THROUGH THE FDEP ON-LINE SYSTEM AT LEAST TWO (2) DAYS BEFORE COMMENCEMENT OF CONSTRUCTION:	F. WHEN A SPILL OF REPORTABLE QUANTITIES IS DISCOVERED ON THE SITE, THE CONTRACTOR SHALL CLEAN UP A MATERIALS AND DISPOSE OF IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS. THE CONTRACTOR SHALL APPROPRIATE AUTHORITIES IN ACCORDANCE WITH APPLICABLE LAWS AND REGULATIONS, THE OWNER AND PROJEC THE CONTRACTOR SHALL RETAIN CLEANUP INFORMATION AS WELL AS DISPOSAL MANIFESTS WITH THEIR SWPPP.
NPDES STORMWATER NOTICES CENTER, MS #2510 FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION, 2600 BLAIR STONE ROAD, TALLAHASSEE, FLORIDA 32399-2400	MATERIALS MANAGEMENT, AND EQUIPMENT STAGING AND MAINTENANCE A. EXCAVATED MATERIAL SHALL NOT BE DEPOSITED IN LOCATIONS WHERE IT COULD BE WASHED AWAY BY HIGH WATEI WATER RUNOFF. STOCKPILED MATERIAL SHALL BE COVERED OR ENCIRCLED WITH SEDIMENT CONTAINMENT DEVICES.
THE CONTRACTOR SHALL SUBMIT A NOTICE OF TERMINATION (NOT) WITHIN 14 CALENDAR DAYS AFTER THE SITE HAS ACHIEVED FINAL STABILIZATION (I.E. ALL DISTURBED SOILS AT THE SITE HAVE BEEN FINAL STABILIZED), TEMPORARY BMPS HAVE BEEN REMOVED, AND STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITY FROM THE SITE AUTHORIZED BY THE PERMIT HAVE BEEN ELIMINATED. AN ENVIRONMENTAL RESOURCE PERMIT IS REQUIRED FOR THE PROJECT. CONTRACTOR SHALL PROVIDE THE PERMIT INFORMATION ON THE NOI APPLICATION.	B. HEAVY CONSTRUCTION EQUIPMENT PARKING AND MAINTENANCE AREAS SHALL BE DESIGNED TO PREVENT OIL, G LUBRICANTS FROM ENTERING SITE DRAINAGE FEATURES INCLUDING STORMWATER COLLECTION AND TREATMEN CONTRACTORS SHALL PROVIDE BROAD DIKES OR SILT SCREENS AROUND, AND SEDIMENT SUMPS WITHIN, SUCH AREAS A TO CONTAIN SPILLS OR OIL, GREASE, LUBRICANTS, OR OTHER CONTAMINANTS. CONTRACTOR SHALL HAVE AVAILABLE
MS4 OPERATOR NAME (IF ANY):	USE, ABSORBENT FILTER PADS TO CLEAN UP SPILLS IMMEDIATELY AFTER ANY OCCURRENCE. C. THE CONTRACTOR SHALL ENSURE THAT ALL TOXIC / HAZARDOUS SUBSTANCES AND CHEMICALS ARE PROPERLY STOP
THE CONTRACTOR SHALL PROVIDE A COPY OF THE NOI AND SUBSEQUENT NOT OR THE ACKNOWLEDGEMENT LETTERS FOR THE NOI OR NOT TO THE MS4 WITHIN 7 DAYS OF RECEIPT. THE CONTRACTOR SHALL ALSO COORDINATE WITH THE MS4 TO ENSURE THAT ALL SPECIFIC REQUIREMENTS ARE MET.	THE WEATHER, AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. THE CONTRACTOR SHALL EN THESE PRODUCTS ARE STORED AND USED IN SUCH A MANNER THAT WILL NOT NEGATIVELY IMPACT STORMWATER, GRO OR PROTECTED SPECIES.
B. WHERE PRACTICAL, STORMWATER SHALL BE CONVEYED BY SWALES. SWALES SHALL BE CONSTRUCTED AS SHOWN ON PLANS.	D. THE CONTRACTOR SHALL ENSURE THAT ALL MATERIALS, EQUIPMENT, DEBRIS, WASTE, TRAILERS, AND OTHER SUPPO ITEMS ARE CONTAINED WITHIN THE PERMITTED LIMITS OF DISTURBANCE. THE CONTRACTOR SHALL ENSURE THAT THE ST USE OF SUCH ITEMS DOES NOT NEGATIVELY IMPACT STORMWATER OR GROUNDWATER.
C. EROSION CONTROL MEASURES SHALL BE EMPLOYED TO MINIMIZE TURBIDITY OF SURFACE WATERS LOCATED DOWNSTREAM OF ANY CONSTRUCTION ACTIVITY. WHILE THE VARIOUS MEASURES REQUIRED WILL BE SITE SPECIFIC, THEY SHALL BE EMPLOYED AS NEEDED IN ACCORDANCE WITH THE FOLLOWING:	OFFSITE VEHICLE TRACKING
 IN GENERAL, EROSION SHALL BE CONTROLLED AT THE FURTHEST PRACTICAL UPSTREAM LOCATION. II. NEW AND EXISTING STORMWATER INLETS AND OUTFALL STRUCTURES SHALL BE PROTECTED DURING CONSTRUCTION. PROTECTION MEASURES SHALL BE EMPLOYED IMMEDIATELY AS REQUIRED DURING THE VARIOUS STAGES OF CONSTRUCTION. III. PERIMETER EROSION CONTROL DEVICES SHALL REMAIN IN PLACE UNTIL FINAL SITE STABILIZATION HAS BEEN ESTABLISHED 	A. THE CONTRACTOR SHALL ENSURE THAT THE CONSTRUCTION EXIT IS USED BY ALL VEHICLES AND EQUIPMENT ENTERING THE JOBSITE. THE CONTRACTOR SHALL MONITOR AND MAINTAIN THE CONSTRUCTION EXIT TO ENSURE THAT NO SOILS AI OFFSITE BY TIRES OR TRACKS, AND THAT NO SOILS ARE SPILLED BY TRUCKS OR EQUIPMENT LEAVING THE SITE. ALL T SPILLED SOILS SHALL BE SHOVELED OR SWEPT FROM THE ROADWAY AND RETURNED TO THE SITE. WATER SHALL NOT CLEAN THE SOILS FROM THE ROADWAY UNLESS THE WATER AND SOILS ARE RECOVERED BY THE USE OF A VACUUM SIMILAR DEVICE.
D. CLEARING AND GRUBBING OPERATIONS SHALL BE CONTROLLED SO AS TO MINIMIZE UNPROTECTED ERODIBLE AREAS EXPOSED TO WEATHER. GENERAL EROSION CONTROL BMP'S SHALL BE EMPLOYED TO MINIMIZE SOIL EROSION AND OFF-SITE SEDIMENTATION. WHILE THE VARIOUS TECHNIQUES REQUIRED WILL BE SITE AND PLAN SPECIFIC, THEY SHOULD BE EMPLOYED PRIOR TO ANY CONSTRUCTION ACTIVITY.	<u>FERTILIZERS, HERBICIDES AND PESTICIDES</u> A. THE CONTRACTOR SHALL ENSURE THAT ALL FERTILIZERS, HERBICIDES, PESTICIDES AND SIMILAR PRODUCTS ARE
E. THE CONTRACTOR SHALL FURNISH, INSTALL PER THE SEQUENCE OF CONSTRUCTION, MAINTAIN AND SUBSEQUENTLY REMOVE, ALL NECESSARY TEMPORARY BMPS. THE CONTRACTOR WILL FURNISH AND INSTALL ALL NECESSARY PERMANENT BMPS.	STORED, OUT OF THE WEATHER, AND APPLIED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. THE C SHALL ENSURE THAT THESE PRODUCTS ARE USED IN SUCH A MANNER THAT WILL NOT NEGATIVELY IMPACT ST GROUNDWATER OR PROTECTED SPECIES.
F. THE CONTRACTOR SHALL ADJUST, ADD OR MODIFY BMPS AS NECESSARY TO COMPLY WITH THE INTENT OF THE GENERIC NPDES PERMIT AND THE SWPPP FOR NO ADDITIONAL COMPENSATION. THE CONTRACTOR SHALL CONSULT WITH THE ENGINEER PRIOR TO ADJUSTING, ADDING OR MODIFYING BMPS THAT AFFECT THE HYDRAULICS OF THE SITE OR BEFORE ADDING BMPS NOT DETAILED IN THE SWPPP.	B. NUTRIENTS SHALL BE APPLIED ONLY AT RATES NECESSARY TO ESTABLISH AND MAINTAIN VEGETATION.
G. THE CONTRACTOR IS ADVISED THAT THE CONTRACT DRAWINGS ONLY INDICATE EROSION, SEDIMENT, AND TURBIDITY CONTROLS AT LOCATIONS DETERMINED IN THE DESIGN PROCESS. HOWEVER, THE CONTRACTOR IS REQUIRED TO PROVIDE ANY ADDITIONAL CONTROLS NECESSARY TO PREVENT THE POSSIBILITY OF	INSPECTIONS AND MAINTENANCE A. THE CONTRACTOR SHALL INSPECT BMPS (I.E. DISCHARGE LOCATIONS, CONSTRUCTION EXIT, PERIMETER CONTROLS, INLE PROTECTION, STABILIZATION, EROSION CONTROL, DOCUMENTATION, WASTE DISPOSAL AREAS, MATERIAL STORAGE AREA ENSURE THAT BMPS ARE NOT CAUSING OR CONTRIBUTION TO VIOLATIONS OF WATER QUALITY STANDARDS OR RESULTIN
SILTING ANY ADJACENT LOWLAND PARCEL OR RECEIVING WATER. H. EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE PLACED PRIOR TO, OR AS THE FIRST STEP IN CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE	OFFSITE SEDIMENTATION; ENSURE THAT BMPS ARE INSTALLED, MAINTAINED AND OPERATING CORRECTLY AND EFFECTIV ENSURE THAT BMPS ASSOCIATED WITH STORAGE AND WASTE DISPOSAL AREAS ARE BEING USED AND MAINTAINED PROP ENSURE THAT THE CONSTRUCTION EXIT IS FUNCTION PROPERLY TO PREVENT OFFSITE TRACKING OF SEDIMENT; ENSURE
FOR COMPLYING WITH ALL EROSION CONTROL MEASURES SHOWN ON THE PLANS. THE EROSION CONTROL SYSTEM DESCRIBED WITHIN THE CONSTRUCTION DOCUMENTS SHOULD BE CONSIDERED TO REPRESENT THE MINIMUM ACCEPTABLE STANDARDS FOR THIS PROJECT. ADDITIONAL EROSION CONTROL MEASURES MAY BE REQUIRED DEPENDENT UPON THE STAGE OF CONSTRUCTION, THE SEVERITY OF THE RAINFALL EVENT AND/OR AS DEEMED NECESSARY AS A RESULT OF ON-SITE INSPECTIONS BY THE OWNER. THEIR REPRESENTATIVES. OR THE APPLICABLE JURISDICTIONAL AUTHORITIES. THESE ADDITIONAL	EROSION PREVENTION MEASURES ARE MAINTAINED TO PREVENT VISIBLE EROSION OF DISTURBED AREAS AND SEDIMENT. THE DISCHARGE POINTS; AND DETERMINE IF CONSTRUCTION ACTIVITIES HAVE ALTERED THE EFFECTIVENESS OF BMPS. II MUST BE COMPLETED AT LEAST ONCE EVERY SEVEN (7) CALENDAR DAYS, AND WITHIN 24 HOURS AFTER A RAINSTORM OF
MEASURES (IF NEEDED) SHALL BE INSTALLED AT NO ADDITIONAL COST TO THE OWNER. IT SHOULD BE NOTED THAT THE MEASURES IDENTIFIED ON THIS PLAN ARE ONLY SUGGESTED BEST MANAGEMENT PRACTICES (BMPS). THE CONTRACTOR SHALL PROVIDE POLLUTION PREVENTION AND EROSION CONTROL MEASURES AS SPECIFIED IN FDOT INDEXES #100 THROUGH #102 AND AS NECESSARY FOR EACH SPECIFIC APPLICATION. IT IS THE CONTRACTOR'S ULTIMATE RESPONSIBILITY TO ASSURE THAT THE STORMWATER DISCHARGE FROM THE SITE DOES NOT EXCEED THE TOLERANCES ESTABLISHED BY ANY OF THE	INCHES OR GREATER EVEN IF IT RAINS ON THE WEEKEND OR A HOLIDAY. B. THE CONTRACTOR SHALL REPORT ALL INSPECTION FINDINGS AND CORRECTIVE ACTIONS TAKEN AS A RESULT OF THE USING THE STORMWATER POLLUTION PREVENTION PLAN INSPECTION REPORT FORM PROVIDED BY FDEP OR AN EQUIVA INSPECTION REPORTS SHALL BE SIGNED BY THE INSPECTOR AND A RESPONSIBLE AUTHORITY AS DEFINED BY 1
APPLICABLE JURISDICTIONAL AUTHORITIES. I. THE CONTRACTOR SHALL KEEP THE SWPPP CURRENT AT ALL TIMES. THE CONTRACTOR SHALL SIGN AND DATE ANY CHANGES TO THE SWPPP AND KEEP	INSPECTION REPORTS SHALL BE MAINTAINED WITH THE SWPPP. THE INSPECTOR MUST BE A QUALIFIED EROSION AN CONTROL INSPECTOR AS DEFINED BY THE FLORIDA DEPARTMENT OF ENVIRONMENTAL PROTECTION.
THEM AS ATTACHMENTS TO THE ORIGINAL PLAN. WHENEVER ANY OF THE FOLLOWING EVENTS OCCUR, THE CONTRACTOR SHALL UPDATE THE SWPPP WITHIN 7 DAYS: I. THERE IS A CHANGE IN DESIGN, CONSTRUCTION OPERATION OR MAINTENANCE THAT HAS A SIGNIFICANT EFFECT ON THE DISCHARGE FROM THE PROJECT	C. ANY MAINTENANCE, REPAIR AND NECESSARY REVISIONS TO BMP ITEMS SHALL BE ADDRESSED IN A TIMELY MANNER, BUT LATER THAN 7 CALENDAR DAYS FOLLOWING THE INSPECTION OR IDENTIFICATION OF THE ISSUE. UNLESS OTHERWISI ACCUMULATED SEDIMENTS SHOULD BE REMOVED BEFORE THEY REACH ONE-HALF OF THE CAPACITY OF THE CONTROL D
II. THERE IS A NEW DISCHARGE POINT OUR OUTFALL III. THERE IS A CHANGE IN THE LOCATION OF A DISCHARGE POINT OF OUTFALL IV. AN INSPECTION REVEALS THAT BMPS ARE INEFFECTIVE AT ELIMINATING OR MINIMIZING POLLUTANTS IN THE STORMWATER DISCHARGED FROM THE SITE. V. THERE IS A NEW SUBCONTRACTOR IMPLEMENTING ANY PORTION OF THE SWPPP VI. A RELEASE CONTAINING A HAZARDOUS SUBSTANCE IN AN AMOUNT EQUAL TO OR GREATER THAN A REPORTABLE QUANTITY OCCURS DURING A 24-HOUR	ALLOWABLE NON-STORMWATER DISCHARGES THE GENERIC PERMIT FOR STORMWATER DISCHARGES ASSOCIATED WITH CONSTRUCTION ACTIVITIES PROHIBIT MOST NON-STORMWATER DISCHARGES DURING THE CONSTRUCTION PHASE. CERTAIN DISCHARGES ARE ALLOWED BY THE PER PROVIDED APPROPRIATE BMP'S ARE UTILIZED AND THE DISCHARGE DOES NOT CAUSE OR CONTRIBUTE TO A VIOLATION O
PERIOD J. THE CONTRACTOR SHALL ENSURE THAT THE CONTRACTOR AND ALL SUBCONTRACTORS RESPONSIBLE FOR IMPLEMENTING SWPPP CONTROL MEASURES FILL	QUALITY STANDARDS. ALLOWABLE NON-STORMWATER DISCHARGES THAT OCCUR DURING CONSTRUCTION ON THIS PRO PART 3.2 OF THE GENERIC PERMIT ARE: DISCHARGES FROM FIRE FIGHTING ACTIVITIES.
OUT THE CONTRACTOR / SUBCONTRACTOR CERTIFICATION TABLE INCLUDED IN THIS SWPPP.	FIRE HYDRANT FLUSHINGS. WATERS WITHOUT DETERGENTS USED TO SPRAY OFF LOOSE SOLIDS FROM VEHICLES. WATERS USED TO CONTROL DUST.
BMPS AND PRIOR TO GROUND DISTURBING ACTIVITIES. THE CONTRACTOR SHALL COMPLETE THE TABLE WITH ANTICIPATED DATES IN WHICH THE BMP WILL BE UTILIZED OR THE ACTIVITY WILL OCCUR. TURBIDITY	POTABLE WATER SOURCES SUCH AS WATERLINE FLUSHINGS. LANDSCAPE IRRIGATION AND DRAINAGE. ROUTINE EXTERNAL BUILDING WASHDOWN PROVIDED NO DETERGENTS ARE USED.
A. TURBIDITY REDUCTION TO NO MORE THAN 29 NTUS ABOVE BACKGROUND LEVEL PRIOR TO DISCHARGE OFF SITE.	PAVEMENT WASHWATERS THAT DO NOT CONTAIN DETERGENTS, LEAKS, SPILLS OF TOXIC OR HAZARDOUS MATERIALS. AIR CONDITIONING CONDENSATE. SPRING WATER.
B. CONTRACTOR TO FILE FOR A FDEP NOTICE OF INTENT (NOI) WITHIN 14 DAYS OF CONSTRUCTION COMPLETION.	FOUNDATION OR FOOTING DRAIN FLOWS THAT ARE NOT CONTAMINATED WITH PROCESS MATERIAL SUCH AS SOLVENTS NONCONTAMINATED GROUND WATER ASSOCIATED WITH DEWATERING ACTIVITIES AS DESCRIBED IN PART 3.4 OF THE G PERMIT.
WITH FDOT SEC. 985)	ANCE



DO NOT DEPLOY SILT FENCES IN A MANNER THAT WILL ACT AS A DAM ACROSS PERMANENT FLOWING WATERCOURSES. SILT FENCES ARE TO BE USED AT UPLAND LOCATIONS AND AS TURBIDITY BARRIERS USED AT PERMANENT BODIES OF WATER.

EROSION CONTROL SILT FENCE


N.T.S.





OWS THAT ARE NOT CONTAMINATED WITH PROCESS MATERIAL SUCH AS SOLVENTS. R ASSOCIATED WITH DEWATERING ACTIVITIES AS DESCRIBED IN PART 3.4 OF THE GENERIC


-ORIGINAL POST POSITIONS


-PRINCIPAL POST POSITION (CANTED 20° TOWARD FLOW)



















	C		Des Drav Che		0 0
sr C	HIS SHE CONSTR OMPLE		cked: No.:		at mology
	UCTI				
et N	ON V		В. Е. 16		C Findineering that works
lo.	VITHO		 √ . SII . SII . SII . O24/ 		P. 850.215.1285 • F. 850.215.1286
	JUT		_CC DOF 016	Flizabeth S Moore PE	450 Magnolia Avenue, Panama City, FL 32401
		CITY OF PARKER, BAY COUNTY, FLORIDA	X RE -2	FL License No.: 57607	CA Number: 31422





REQUIRED LENGTH OF RESTRAINED JOINT PIPE FOR P.V.C. PIPE

9 8 8 8

- H = 1


4 H b I


MAIN PIPE	HOR	IZ. BE	ENDS		*TEES					ערוס		
SIZE	90°	45°	22.5°		SIZ		NGTH		SIZ		NGTH	PLU
36	106	44	21	X36	X30 102	X24 39		X16	X30 78	X24 141	X20 175	25
30	93	39	19	X30 132	X24 68	X20 22	X16	X12	X24 78	X20 121	X16 156	22
24	79	33	16	X24 99	X20 53	X16	X12	X10	X20 56	X16 101	X12 137	18
20	68	29	14	X20 75	X16 26	X12	X10	X8	X16 56	X12 100	X10 117	15
16	57	24	12	X16 51	X12	X10	X8		X12 56	X10 78	X8 96	13
12	45	19	9	X12 25	X10	X8	X6		X10 30	X8 54	X6 74	10
10	39	16	8	X10 11	X8	X6			X8 29	X6 53	X4 71	8
8	33	14	/	X8	X6	X4			X6 31	X4 52		7
6	25	11	5	X6	X4				X4 29			5
4	18	8	4	X4								3

*MAIN TO BE RESTRAINED 20' ON EACH SIDE OF BRANCH

NOTES:

- 1. RESTRAIN TO NEXT FULL JOINT BEYOND GIVEN LENGTH.
- 2. RESTRAIN 11.25° BENDS 50% OF LENGTH FOR 22.5° BENDS.
- 3. ALL VALVES AND FITTINGS SHALL BE RESTRAINED TO THE CONNECTING SECTIONS OF PIPE.
- 4. PIPE ADJACENT TO IN-LINE VALVES 10" AND SMALLER SHALL BE RESTRAINED FOR 20' ON EACH SIDE, INCLUDING THE VALVE-TO-PIPE CONNECTION. ALL PIPE ADJACENT TO IN-LINE VALVES 12" AND LARGER SHALL BE RESTRAINED FOR A DISTANCE 1/4 OF REQ'D PLUG (DEAD END) LENGTH ON EACH SIDE, INCLUDING THE VALVE-TO-PIPE CONNECTION.
- 5. PIPE SIZES ARE GIVEN IN INCHES.
- 6. PIPE LENGTHS ARE GIVEN IN FEET.
- 7. LENGTHS SHOWN ARE FOR A TEST PRESSURE OF 150 PSI.
- 8. RESTRAINED LENGTHS FOR TEES REPRESENTS LENGTH ON BRANCH. RESTRAINED LENGTHS FOR REDUCERS REPRESENTS LENGTH ON LARGE END OF REDUCER.
- 9. RESTRAINED LENGTHS ARE TO BE USED FOR POTABLE WATER. 10. THE RESTRAINED LENGTHS SHOWN IN THESE TABLES ARE BASED ON THE USE OF LIGHTLY
- COMPACTED CLEAN SAND WITH AT LEAST A 95% COARSE PARTICLE CONTENT. ACTUAL SOIL CONDITIONS MUST BE DETERMINED BY THE ENGINEER OF RECORD AND THE RESTRAINED LENGTHS MODIFIED ACCORDINGLY. SAFETY FACTOR OF 1.5:1 TO BE CALCULATED WITH A "SM" SOIL TYPE AND TRENCH TYPE "3".





-6" THICK CONCRETE

VALVE BOX

-1/2" HOLE IN CONC.

-END OF 12 GA. WIRE

TO VALVE BOX

(4 TOTAL)

-1/2" HOLE IN CONC. NEXT

-2-#3 BAR EACH WAY

COMPLETELY COVERING WIRE

-ADJUSTABLE CAST IRON

-12 GA. TRACER WIRE

VALVE BOX

NEXT TO VALVE BOX

-VALVE BOX

AND COVER

(TYP.)

PAD TYPICAL EACH

— 24"SQ. — 🗖